

Certificate of compliance

Applicant: Huawei Technologies Co., Ltd.

Administration Building, Headquarters of Huawei Technologies Co.,

Ltd., Bantian, Longgang District, Shenzhen, 518129,

P.R.C

Product: SOLAR INVERTER

Model: SUN2000-3KTL-M0, SUN2000-4KTL-M0,

SUN2000-5KTL-M0, SUN2000-6KTL-M0, SUN2000-8KTL-M0, SUN2000-10KTL-M0, SUN2000-3KTL-M1, SUN2000-4KTL-M1, SUN2000-5KTL-M1, SUN2000-6KTL-M1, SUN2000-8KTL-M1, SUN2000-10KTL-M1

Use in accordance with regulations:

Automatic disconnection device with three-phase mains surveillance in accordance with Engineering Recommendation G98/1 for photovoltaic systems with a three-phase parallel coupling via an inverter in the public mains supply. The automatic disconnection device is an integral part of the aforementioned inverter. This serves as a replacement for the disconnection device with isolating function that can access the distribution network provider at any time.

Applied rules and standards:

Engineering Recommendation G98/1-1:2018

Requirements for the connection of Fully Type Tested Micro-generators (up to and including 16 A per phase) in parallel with public Low Voltage Distribution Networks

DIN V VDE V 0126-1-1:2006-02 (Functional safety)

Automatic disconnection device between a generator and the public low-voltage grid

At the time of issue of this certificate the safety concept of an aforementioned representative product corresponds to the valid safety specifications for the specified use in accordance with regulations.

Report number: PVUK180906N022

Certificate number: U19-0112
Date of issue: 2019-02-20

Certification body

Holger Schaffer

Certification body of Bureau Veritas Consumer Products Services Germany GmbH Accredited according to DIN EN ISO/IEC 17065



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

Type Approval and declaration of	compliance wit	h the requirem	ents of Engine	ering Recomm	endation G98/1	l.			
Manufacturer / applicant:	Huawei Techn	Huawei Technologies Co., Ltd.							
		Administration Building, Headquarters of Huawei Technologies Co., Ltd., Bantian, Longgang District, Shenzhen, 518129, P.R.C							
Generating Unit technology	SOLAR INVER	SOLAR INVERTER							
Rated values	SUN2000- 3KTL-M0 SUN2000-	3KTL-M0 4KTL-M0 5KTL-M0 6KTL-M0 8KTL-M0 10KTL-M							
	3KTL-M1	4KTL-M1	5KTL-M1	6KTL-M1	8KTL-M1	10KTL-M1			
Nominal rated capacity	3,0 kW	4,0 kW	5,0 kW	6,0 kW	8,0 kW	10,0 kW			
Maximum capacity	3,3 kVA	4,4 kVA	5,5 kVA	6,6 kVA	8,8 kVA	11,0 kVA			
Rated voltage			230V	/400V					
Firmware version		V100R001							
Measurement period:			2018-09-06 b	is 2018-12-16					

Description of the structure of the power generation unit:

The power generation unit is equipped with a PV and line-side EMC filter. The power generation unit has no galvanic isolation between DC input and AC output. Output switch-off is performed with single-fault tolerance based on two series-connected relays in line and neutral. This enables a safe disconnection of the power generation unit from the network in case of error.

The above stated Generating Units are tested according the requirements in the Engineering Recommendation G98/1-1. Any modification that affects the stated tests must be named by the manufacturer/supplier of the product to ensure that the product meets all requirements of the Engineering Recommendation G98/1-1.



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1 Nr. PVUK180906N022

Operating Range.	
Connection:	Always connected
Limit:	Always connected
Test 1	Voltage = 85% of nominal (195,5 V) Frequency = 47,5 Hz Power Factor = 1 Period of test 90 minutes
Connection:	Always connected
Limit:	Always connected
Test 2	Voltage = 110% of nominal (253 V) Frequency = 51,5 Hz Power Factor = 1 Period of test 90 minutes
Connection:	Always connected
Limit:	Always connected
Test 3	Voltage = 110% of nominal (253 V) Frequency = 52,0 Hz Power Factor = 1 Period of test 15 minutes
Connection:	Always connected
Limit:	Always connected

Protection. Voltag	ge tests.									
Phase 1										
Function	Set	ting	Trip	test	No trip	test				
	Voltage [V]	Time delay [s]	Voltage [V]	Time delay [s]	Voltage / time	Confirm no trip				
U/V	184	2,5	182,9	2,572	188V / 3,5s	No trip				
					180V / 2,48s	No trip				
O/V stage 1	262,2	1,0	261,0	1,062	258,2V 2,0s	No trip				
O/V stage 2	273,7	0,5	272,2	0,563	269,7V 0,98s	No trip				
	·				277,7V 0,48s	No trip				



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

Protection. Voltag	e tests.					
			Phase 2			
Function	Set	ting	Trip	test	No trip	test
	Voltage [V]	Time delay [s]	Voltage [V]	Time delay [s]	Voltage / time	Confirm no trip
U/V	184	2,5	184,9	2,552	188V / 3,5s	No trip
					180V / 2,48s	No trip
O/V stage 1	262,2	1,0	263,2	1,077	258,2V 2,0s	No trip
O/V stage 2	273,7	0,5	275,0	0,583	269,7V 0,98s	No trip
					277,7V 0,48s	No trip

Protection. Voltage	Protection. Voltage tests.									
Phase 3										
Function	Set	ting	Trip	test	No trip	test				
	Voltage [V]	Time delay [s]	Voltage [V]	Time delay [s]	Voltage / time	Confirm no trip				
U/V	184	2,5	184,8	2,556	188V / 3,5s	No trip				
					180V / 2,48s	No trip				
O/V stage 1	262,2	1,0	262,1	1,074	258,2V 2,0s	No trip				
O/V stage 2	273,7	0,5	274,1	0,558	269,7V 0,98s	No trip				
					277,7V 0,48s	No trip				

Note. For Voltage tests the Voltage required to trip is the setting $\pm 3,45$ V. The time delay can be measured at a larger deviation than the minimum required to operate the protection. The No trip tests need to be carried out at the setting ± 4 V and for the relevant times as shown in the table above to ensure that the protection will not trip in error.



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

Protection. Freque	Protection. Frequency tests.										
Function	Set	ting	Trip	test	No trip	test					
	Frequency Time delay Frequency [Hz] [S] [Hz]		Time delay [s]	Frequency / time	Confirm no trip						
U/F stage 1	47,5	20	47,5	20,065	47,7Hz / 25s	No trip					
U/F stage 2	47	0,5	47,0	0,567	47,2Hz / 19,98s	No trip					
					46,8Hz / 0,48s	No trip					
O/F stage 2	52	0,5	52,0	0,560	51,8Hz / 89,98s	No trip					
					52,2Hz / 0,48s	No trip					

Note. For Frequency Trip tests the Frequency required to trip is the setting ± 0.1 Hz. In order to measure the time delay a larger deviation than the minimum required to operate the projection can be used. The "No-trip tests" need to be carried out at the setting ± 0.2 Hz and for the relevant times as shown in the table above to ensure that the protection will not trip in error.

Protection. Loss of N	Protection. Loss of Mains.										
Inverters tested according to BS EN 62116.											
Balancing load on islanded network 33% of -5% Q -5% Q -5% P +5% Q +5% Q Test 22 66% of -5% P +5% Q +5% Q +5% Q Test 5 100% of -5% P +5% Q +5% Q +5% Q Test 31 100% of -5% P +5% Q Test 31 <											
Trip time. Ph1 fuse removed [s]	0,169	0,173	0,291	0,255	0,248	0,270					
Trip time. Ph2 fuse removed [s]	0,169	0,173	0,291	0,255	0,248	0,270					
Trip time. Ph3 fuse removed [s]	0,169	0,173	0,291	0,255	0,248	0,270					

Note. Trip time limit is 0,5s. For technologies which have a substantial shut down time this can be added to the 0,5s in establishing that the trip occurred in less than 0,5s maximum. Shut down time could therefore be up to 1,0s for these technologies.



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1

Protection. Re-connection time	r.					
Test should prove that the reconnuithin the stage 1 settings of table		n no less thar	20 secon	ds for restoration of volt	age and frequency to	
	Unde	r Voltage (18	2V)			
Time delay	setting			Measured delay		
209	3			121s		
	Over	Voltage (266,	2V)			
Time delay	setting			Measured delay		
20s	3			125s		
	Under F	requency (47	,4Hz)			
Time delay	setting			Measured delay		
20s	3		125s			
	Over F	requency (52	1Hz)			
Time delay	setting			Measured delay		
20s	3		125s			
	Checks on no reconnect of table 1.	ction when vol	age or free	quency is brought to just	outside stage 1 limits	
	At 266,2V				At 52,1Hz	
Confirmation that the Generating Unit does not reconnect.	No reconnection	No reconr	No reconnection No reconnection No re			


Protection. Frequency change, Stability test.								
	Start Frequency [Hz]	Change	Test Duration	Confirm no trip				
Positive Vector Shift	49,5	+50 degrees		No trip				
Negative Vector Shift	50,5	-50 degrees		No trip				
Positive Frequency drift	49,0	+0,95Hz/sec	2,1s	No trip				
Negative Frequency drift	51,0	-0,95Hz/sec	2,1s	No trip				






Extract from test report according to the Engineering Recommendation G98/1-1


Limited Frequency Sensitive M	Mode – Over F	requency					
1-min mean value [Hz]:	a) 50,00	b) 50,45	c) 50,70	d) 51,15	e) 50,70	f) 50,45	g) 50,00
1. Measurement a) to g): Activ	e power outpu	ıt > 80% Pn					
Frequency [Hz]:	50,00	50,45	50,70	51,15	50,70	50,45	50,00
PM [kW]:	N/A	9,880	9,390	8,480	9,390	9,880	N/A
PE60 [kW]:	10,000	9,884	9,384	8,483	9,384	9,884	10,000
∆PE60/PM [%]:	N/A	0,06	0,06	0,07	0,06	0,04	N/A
Limit ΔP/P _{1min} :				+ 10 % of PM			
2. Measurement a) to g): Activ	e power outpu	ıt 40% and 60	% after freezi	ing > 80% Pn			
Frequency [Hz]:	50,00	50,45	50,70	51,15	50,70	50,45	50,00
PM [kW]:	N/A	5,001	4,751	4,295	4,748	5,003	N/A
PE60 [kW]:	5,070	5,003	4,750	4,293	4,750	5,003	5,558
∆PE60/PM [%]:	N/A	0,02	0,01	0,02	0,02	0,01	N/A
Limit ΔP/P _{1min} :				+ 10 % of PM			
Graph of Measurement 1.: Act	ive power out	put > 80% Pn					
12000					51.	40	
10000 -					- 51.		
0000	_	$\neg \Box$			- 51.	00	








Extract from test report according to the Engineering Recommendation G98/1-1





Output Power with falling Frequency	Output Power with falling Frequency							
5-min mean value (each)	a) 50 ± 0,01 Hz	b) - 0,4 to - 0,5 Hz	c) - 2,4 to - 2,5 Hz					
Frequency [Hz]:	50,00	49,55	47,55					
Active power [W]:	9995	9995	9996					
ΔP/PM [%] per 1 Hz:			0					





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

ower Quality. H	armonics.					
			Phase 1			
SSEC	G rating per phase	(rpp)	SUN2000	-3KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output	_	
	0,6	kW	1,0	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,032	0,669	0,008	0,189	1,080	
3rd	0,030	0,627	0,012	0,278	2,300	
4th	0,022	0,460	0,006	0,140	0,430	
5th	0,015	0,314	0,009	0,207	1,140	
6th	0,012	0,251	0,005	0,117	0,300	
7th	0,013	0,272	0,007	0,157	0,770	
8th	0,011	0,230	0,004	0,102	0,230	
9th	0,013	0,272	0,009	0,196	0,400	
10th	0,012	0,251	0,005	0,117	0,184	
11th	0,011	0,230	0,007	0,152	0,330	
12th	0,012	0,251	0,005	0,113	0,153	
13th	0,012	0,251	0,006	0,141	0,210	
14th	0,010	0,209	0,005	0,115	0,131	
15th	0,012	0,251	0,007	0,153	0,150	
16th	0,009	0,188	0,004	0,098	0,115	
17th	0,009	0,188	0,007	0,160	0,132	
18th	0,008	0,167	0,005	0,122	0,102	
19th	0,008	0,167	0,006	0,139	0,118	
20th	0,007	0,146	0,005	0,111	0,092	
21th	0,008	0,167	0,006	0,131	0,107	0,160
22th	0,006	0,125	0,005	0,113	0,084	·
23th	0,006	0,125	0,007	0,170	0,098	0,147
24th	0,006	0,125	0,006	0,144	0,077	·
25th	0,006	0,125	0,007	0,167	0,090	0,135
26th	0,004	0,084	0,006	0,136	0,071	-, -, -,
27th	0,005	0,105	0,006	0,135	0,083	0,124
28th	0,003	0,063	0,006	0,131	0,066	,
29th	0,005	0,105	0,006	0,141	0,078	0,117
30th	0,004	0,084	0,006	0,132	0,061	,
31th	0,004	0,084	0,005	0,126	0,073	0,109
32th	0,003	0,063	0,007	0,152	0,058	,
33th	0,013	0,272	0,007	0,150	0,068	0,102
34th	0,003	0,063	0,004	0,092	0,054	-, -
35th	0,012	0,251	0,005	0,111	0,064	0.096
36th	0,004	0,084	0,005	0,106	0,051	2,223
37th	0,017	0,355	0,005	0,104	0,061	0.091
38th	0,004	0,084	0,004	0,095	0,048	2,221
39th	0,016	0,335	0,004	0,097	0,058	0.087
40th	0,004	0,084	0,004	0,086	0,046	2,221





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

ower Quality. H	armonics.					
			Phase 2			
SSEC	G rating per phase	(rpp)	SUN2000	-3KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output	_	
	0,6	kW	1,0	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,041	0,857	0,009	0,204	1,080	
3rd	0,034	0,711	0,025	0,576	2,300	
4th	0,019	0,397	0,007	0,156	0,430	
5th	0,013	0,272	0,009	0,210	1,140	
6th	0,011	0,230	0,005	0,125	0,300	
7th	0,010	0,209	0,008	0,177	0,770	
8th	0,010	0,209	0,005	0,123	0,230	
9th	0,013	0,272	0,007	0,165	0,400	
10th	0,010	0,209	0,006	0,135	0,184	
11th	0,010	0,209	0,007	0,153	0,330	
12th	0,010	0,209	0,005	0,110	0,153	
13th	0,012	0,251	0,006	0,145	0,210	
14th	0,011	0,230	0,005	0,119	0,131	
15th	0,017	0,355	0,007	0,161	0,150	
16th	0,009	0,188	0,005	0,121	0,115	
17th	0,009	0,188	0,007	0,165	0,132	
18th	0,009	0,188	0,006	0,129	0,102	
19th	0,008	0,167	0,006	0,144	0,118	
20th	0,008	0,167	0,005	0,115	0,092	
21th	0,010	0,209	0,008	0,171	0,107	0,160
22th	0,006	0,125	0,005	0,113	0,084	·
23th	0,006	0,125	0,007	0,161	0,098	0,147
24th	0,005	0,105	0,007	0,159	0,077	·
25th	0,005	0,105	0,008	0,174	0,090	0,135
26th	0,004	0,084	0,006	0,145	0,071	
27th	0,005	0,105	0,009	0,195	0,083	0,124
28th	0,003	0,063	0,005	0,124	0,066	·
29th	0,004	0,084	0,006	0,142	0,078	0,117
30th	0,004	0,084	0,006	0,139	0,061	,
31th	0,004	0,084	0,006	0,129	0,073	0,109
32th	0,003	0,063	0,006	0,144	0,058	,
33th	0,015	0,314	0,007	0,148	0,068	0,102
34th	0,003	0,063	0,005	0,105	0,054	
35th	0,012	0,251	0,005	0,111	0,064	0.096
36th	0,004	0,084	0,006	0,126	0,051	2,223
37th	0,018	0,376	0,005	0,104	0,061	0.091
38th	0,004	0,084	0,004	0,101	0,048	2,227
39th	0,020	0,418	0,007	0,168	0,058	0.087
40th	0,004	0,084	0,004	0,089	0,046	2,221






Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 3			
SSE	G rating per phase	(rpp)	SUN2000	-3KTL-M0		
	At 45-55% of		100% of ra	ited output		
	0,6	•		kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lir for odd harmonics and abov
2nd	0,031	0,648	0,006	0,144	1,080	
3rd	0,038	0,795	0,014	0,319	2,300	
4th	0,022	0,460	0,007	0,160	0,430	
5th	0,018	0,376	0,006	0,128	1,140	
6th	0,013	0,272	0,005	0,116	0,300	
7th	0,013	0,272	0,006	0,141	0,770	
8th	0,011	0,230	0,006	0,128	0,230	
9th	0,013	0,272	0,008	0,173	0,400	
10th	0,010	0,209	0,006	0,130	0,184	
11th	0,011	0,230	0,005	0,120	0,330	
12th	0,012	0,251	0,005	0,114	0,153	
13th	0,011	0,230	0,006	0,141	0,210	
14th	0,011	0,230	0,005	0,114	0,131	
15th	0,013	0,272	0,009	0,217	0,150	
16th	0,010	0,209	0,005	0,122	0,115	
17th	0,010	0,209	0,007	0,156	0,132	
18th	0,009	0,188	0,006	0,135	0,102	
19th	0,009	0,188	0,005	0,124	0,118	
20th	0,008	0,167	0,006	0,135	0,092	
21th	0,007	0,146	0,007	0,160	0,107	0,160
22th	0,006	0,125	0,006	0,149	0,084	,
23th	0,007	0,146	0,006	0,148	0,098	0,147
24th	0,005	0,105	0,007	0,156	0,077	,
25th	0,005	0,105	0,007	0,156	0,090	0,135
26th	0,005	0,105	0,007	0,163	0,071	.,
27th	0,005	0,105	0,010	0,218	0,083	0,124
28th	0,004	0,084	0,006	0,142	0,066	,
29th	0,006	0,125	0,005	0,126	0,078	0,117
30th	0,004	0,084	0,005	0,122	0,061	3,111
31th	0,004	0,084	0,005	0,114	0,073	0,109
32th	0,004	0,084	0,005	0,118	0,058	5,100
33th	0,010	0,209	0,013	0,289	0,068	0,102
34th	0,003	0,063	0,005	0,108	0,054	5,152
35th	0,012	0,251	0,005	0,123	0,064	0.096
36th	0,004	0,084	0,005	0,123	0,051	0,000
37th	0,004	0,376	0,005	0,113	0,061	0,091
38th	0,004	0,084	0,005	0,107	0,048	0,001
39th	0,004	0,314	0,003	0,159	0,048	0,087
40th	0,004	0,084	0,007	0,107	0,046	0,007





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

ower Quality. H	wer Quality. Harmonics.									
			Phase 1							
SSEC	G rating per phase	(rpp)	SUN2000	-4KTL-M0						
	At 45-55% of	rated output	100% of ra	ited output						
	0,7	kW	1,3	kW						
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above				
2nd	0,028	0,439	0,038	0,645	1,080					
3rd	0,024	0,376	0,017	0,290	2,300					
4th	0,024	0,376	0,016	0,268	0,430					
5th	0,014	0,220	0,026	0,447	1,140					
6th	0,013	0,204	0,005	0,084	0,300					
7th	0,012	0,188	0,033	0,564	0,770					
8th	0,011	0,173	0,012	0,203	0,230					
9th	0,009	0,141	0,007	0,124	0,400					
10th	0,011	0,173	0,017	0,292	0,184					
11th	0,010	0,157	0,014	0,247	0,330					
12th	0,013	0,204	0,007	0,124	0,153					
13th	0,010	0,157	0,023	0,388	0,210					
14th	0,011	0,173	0,004	0,076	0,131					
15th	0,008	0,125	0,007	0,122	0,150					
16th	0,010	0,157	0,007	0,120	0,115					
17th	0,008	0,125	0,069	1,169	0,132					
18th	0,009	0,141	0,007	0,118	0,102					
19th	0,007	0,110	0,045	0,761	0,118					
20th	0,007	0,110	0,006	0,103	0,092					
21th	0,007	0,110	0,006	0,107	0,107	0,160				
22th	0,008	0,125	0,007	0,111	0,084	·				
23th	0,005	0,078	0,009	0,158	0,098	0,147				
24th	0,006	0,094	0,007	0,120	0,077	·				
25th	0,005	0,078	0,015	0,247	0,090	0,135				
26th	0,005	0,078	0,011	0,188	0,071					
27th	0,005	0,078	0,007	0,127	0,083	0,124				
28th	0,005	0,078	0,011	0,183	0,066	·				
29th	0,005	0,078	0,012	0,210	0,078	0,117				
30th	0,004	0,063	0,009	0,146	0,061	,				
31th	0,004	0,063	0,010	0,163	0,073	0,109				
32th	0,003	0,047	0,020	0,333	0,058	,				
33th	0,011	0,173	0,008	0,134	0,068	0,102				
34th	0,003	0,047	0,014	0,234	0,054	-, -				
35th	0,013	0,204	0,009	0,156	0,064	0.096				
36th	0,004	0,063	0,007	0,121	0,051	2,223				
37th	0,019	0,298	0,012	0,196	0,061	0.091				
38th	0,004	0,063	0,012	0,208	0,048	-,				
39th	0,013	0,204	0,011	0,187	0,058	0.087				
40th	0,004	0.063	0,012	0,198	0,046	2,221				






Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

ower Quality. H	armonics.					
			Phase 2			
SSEC	G rating per phase	(rpp)	SUN2000	-4KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output		
	0,7	kW	1,3	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,040	0,627	0,023	0,391	1,080	
3rd	0,028	0,439	0,010	0,162	2,300	
4th	0,022	0,345	0,016	0,268	0,430	
5th	0,010	0,157	0,027	0,458	1,140	
6th	0,010	0,157	0,005	0,090	0,300	
7th	0,008	0,125	0,029	0,496	0,770	
8th	0,010	0,157	0,016	0,266	0,230	
9th	0,008	0,125	0,016	0,274	0,400	
10th	0,010	0,157	0,018	0,302	0,184	
11th	0,007	0,110	0,014	0,232	0,330	
12th	0,011	0,173	0,008	0,131	0,153	
13th	0,009	0,141	0,022	0,372	0,210	
14th	0,011	0,173	0,007	0,121	0,131	
15th	0,014	0,220	0,006	0,095	0,150	
16th	0,011	0,173	0,007	0,111	0,115	
17th	0,007	0,110	0,069	1,176	0,132	
18th	0,009	0,141	0,006	0,106	0,102	
19th	0,006	0,094	0,045	0,764	0,118	
20th	0,008	0,125	0,007	0,124	0,092	
21th	0,007	0,110	0,008	0,130	0,107	0,160
22th	0,007	0,110	0,007	0,114	0,084	·
23th	0,006	0,094	0,010	0,166	0,098	0,147
24th	0,006	0,094	0,008	0,138	0,077	·
25th	0,005	0,078	0,014	0,245	0,090	0,135
26th	0,004	0,063	0,012	0,198	0,071	
27th	0,007	0,110	0,008	0,136	0,083	0,124
28th	0,005	0,078	0,013	0,220	0,066	
29th	0,005	0,078	0.009	0,152	0,078	0,117
30th	0,004	0,063	0,007	0,123	0,061	,
31th	0,004	0,063	0,008	0,134	0,073	0,109
32th	0,003	0,047	0,010	0,172	0,058	,
33th	0,013	0,204	0,009	0,147	0,068	0,102
34th	0,004	0,063	0,010	0,174	0,054	
35th	0,013	0,204	0,007	0,122	0,064	0.096
36th	0,004	0,063	0,008	0,143	0,051	2,223
37th	0,018	0,282	0,012	0,206	0,061	0.091
38th	0,004	0.063	0,014	0,236	0,048	-,
39th	0,015	0,235	0,008	0,141	0,058	0.087
40th	0,004	0.063	0,013	0,216	0,046	2,221





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 3			
SSE	G rating per phase	(rpp)	SUN2000	-4KTL-M0		
	At 45-55% of		100% of ra	ited output		
	0,7	•		kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lir for odd harmonics and abov
2nd	0,029	0,455	0,031	0,525	1,080	
3rd	0,036	0,565	0,012	0,213	2,300	
4th	0,024	0,376	0,014	0,234	0,430	
5th	0,014	0,220	0,035	0,598	1,140	
6th	0,013	0,204	0,006	0,095	0,300	
7th	0,010	0,157	0,033	0,554	0,770	
8th	0,010	0,157	0,013	0,220	0,230	
9th	0,011	0,173	0,007	0,122	0,400	
10th	0,010	0,157	0,018	0,301	0,184	
11th	0,010	0,157	0,011	0,181	0,330	
12th	0,013	0,204	0,005	0,093	0,153	
13th	0,009	0,141	0,025	0,433	0,210	
14th	0,010	0,157	0,006	0,106	0,131	
15th	0,009	0,141	0,008	0,141	0,150	
16th	0,010	0,157	0,006	0,108	0,115	
17th	0,007	0,110	0,070	1,198	0,132	
18th	0,010	0,157	0,006	0,105	0,102	
19th	0,007	0,110	0,046	0,786	0,118	
20th	0,007	0,110	0,007	0,123	0,092	
21th	0,005	0,078	0,006	0,094	0,107	0,160
22th	0,007	0,110	0,007	0,119	0,084	,
23th	0,005	0,078	0,011	0,179	0,098	0,147
24th	0,006	0,094	0,007	0,118	0,077	,
25th	0,004	0,063	0,014	0,231	0,090	0,135
26th	0,005	0,078	0,009	0,159	0,071	,
27th	0,004	0,063	0,008	0,128	0,083	0,124
28th	0,004	0,063	0,010	0,171	0,066	
29th	0,005	0,078	0,010	0,176	0,078	0,117
30th	0,005	0,078	0,007	0,122	0,061	-,
31th	0,004	0,063	0,007	0,119	0,073	0,109
32th	0,004	0,063	0,014	0,239	0,058	3,.30
33th	0,009	0,141	0,006	0,099	0,068	0,102
34th	0,003	0,047	0,013	0,216	0,054	5,.52
35th	0,013	0,204	0,008	0,141	0,064	0,096
36th	0,004	0,063	0,007	0,116	0,051	0,000
37th	0,018	0,282	0,010	0,174	0,061	0,091
38th	0,004	0,063	0,011	0,195	0,048	0,001
39th	0,012	0,188	0,009	0,154	0,058	0,087
40th	0,004	0,063	0,009	0,149	0,046	5,557





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

ower Quality. H	armonics.					
			Phase 1			
SSEC	G rating per phase	(rpp)	SUN2000	-5KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output		
	0,8	kW	1,6	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,015	0,188	0,015	0,203	1,080	
3rd	0,008	0,100	0,017	0,233	2,300	
4th	0,010	0,125	0,007	0,097	0,430	
5th	0,007	0,088	0,041	0,552	1,140	
6th	0,009	0,113	0,007	0,102	0,300	
7th	0,009	0,113	0,031	0,420	0,770	
8th	0,007	0,088	0,005	0,069	0,230	
9th	0,007	0,088	0,008	0,111	0,400	
10th	0,010	0,125	0,006	0,076	0,184	
11th	0,008	0,100	0,032	0,432	0,330	
12th	0,012	0,151	0,006	0,084	0,153	
13th	0,006	0,075	0,013	0,173	0,210	
14th	0,010	0,125	0,007	0,094	0,131	
15th	0,006	0,075	0,009	0,122	0,150	
16th	0,011	0,138	0,006	0,086	0,115	
17th	0,008	0,100	0,032	0,443	0,132	
18th	0,009	0,113	0,006	0,079	0,102	
19th	0,005	0,063	0,048	0,655	0,118	
20th	0,007	0,088	0,008	0,112	0,092	
21th	0,005	0,063	0,011	0,144	0,107	0,160
22th	0,008	0,100	0,006	0,085	0,084	·
23th	0,004	0,050	0,012	0,165	0,098	0,147
24th	0,006	0,075	0,007	0,092	0,077	·
25th	0,004	0,050	0,012	0,160	0,090	0,135
26th	0,004	0,050	0,009	0,118	0,071	
27th	0,004	0,050	0,009	0,119	0,083	0,124
28th	0,005	0,063	0,008	0,103	0,066	·
29th	0,004	0,050	0,010	0,130	0,078	0,117
30th	0,005	0,063	0,010	0,142	0,061	,
31th	0,005	0,063	0,009	0,120	0,073	0,109
32th	0,003	0,038	0,010	0,132	0,058	
33th	0,013	0,163	0,009	0,125	0,068	0,102
34th	0,003	0,038	0,008	0,108	0,054	
35th	0,017	0,213	0,009	0,121	0,064	0.096
36th	0,004	0,050	0,009	0,128	0,051	2,223
37th	0,015	0,188	0,007	0,102	0,061	0.091
38th	0,003	0,038	0,010	0,141	0,048	2,221
39th	0,017	0,213	0,009	0,127	0,058	0.087
40th	0,003	0,038	0.008	0,103	0,046	2,221





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 2			
SSE	G rating per phase	(rpp)	SUN2000	-5KTL-M0		
	At 45-55% of	rated output	100% of ra	ted output	1	
	0,8	•		kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lin for odd harmonics and abov
2nd	0,022	0,276	0,010	0,140	1,080	
3rd	0,008	0,100	0,025	0,345	2,300	
4th	0,010	0,125	0,007	0,101	0,430	
5th	0,007	0,088	0,036	0,492	1,140	
6th	0,008	0,100	0,007	0,093	0,300	
7th	0,006	0,075	0,030	0,413	0,770	
8th	0,007	0,088	0,006	0,078	0,230	
9th	0,005	0,063	0,007	0,091	0,400	
10th	0,009	0,113	0,006	0,081	0,184	
11th	0,005	0,063	0,030	0,405	0,330	
12th	0,010	0,125	0,006	0,087	0,153	
13th	0,007	0,088	0,014	0,194	0,210	
14th	0,009	0,113	0,007	0,089	0,131	
15th	0,009	0,113	0,009	0,118	0,150	
16th	0,010	0,125	0,007	0,097	0,115	
17th	0,005	0,063	0,029	0,392	0,132	
18th	0,009	0,113	0,009	0,123	0,102	
19th	0,006	0,075	0,045	0,607	0,118	
20th	0,007	0,088	0,010	0,134	0,092	
21th	0,010	0,125	0,008	0,103	0,107	0,160
22th	0,007	0,088	0,007	0,098	0,084	
23th	0,004	0,050	0,011	0,143	0,098	0,147
24th	0,006	0,075	0,007	0,092	0,077	·
25th	0,004	0,050	0,012	0,164	0,090	0,135
26th	0,004	0,050	0,007	0,102	0,071	,
27th	0,005	0,063	0,008	0,109	0,083	0,124
28th	0,005	0,063	0,008	0,102	0,066	
29th	0,004	0,050	0,007	0,100	0,078	0,117
30th	0,004	0,050	0,011	0,148	0,061	
31th	0,006	0,075	0,007	0,096	0,073	0,109
32th	0,003	0,038	0,010	0,130	0,058	,
33th	0,013	0,163	0,009	0,117	0,068	0,102
34th	0,004	0,050	0,009	0,118	0,054	,
35th	0,017	0,213	0,008	0,112	0,064	0,096
36th	0,004	0,050	0,009	0,118	0,051	,
37th	0,015	0,188	0,010	0,134	0,061	0,091
38th	0,004	0,050	0,010	0,133	0,048	,
39th	0,022	0,276	0,008	0,112	0,058	0,087
40th	0,004	0,050	0,010	0,135	0,046	





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 3			
SSEC	G rating per phase	(rpp)	SUN2000	-5KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output		
	0,8	kW	1,6	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,014	0,176	0,015	0,200	1,080	
3rd	0,024	0,301	0,009	0,126	2,300	
4th	0,008	0,100	0,007	0,095	0,430	
5th	0,007	0,088	0,048	0,654	1,140	
6th	0,009	0,113	0,005	0,070	0,300	
7th	0,007	0,088	0,035	0,482	0,770	
8th	0,007	0,088	0,006	0,079	0,230	
9th	0,008	0,100	0,006	0,079	0,400	
10th	0,009	0,113	0,005	0,069	0,184	
11th	0,008	0,100	0,029	0,398	0,330	
12th	0,012	0,151	0,005	0,075	0,153	
13th	0,008	0,100	0,010	0,137	0,210	
14th	0,008	0,100	0,006	0,083	0,131	
15th	0,008	0,100	0,007	0,103	0,150	
16th	0,009	0,113	0,007	0,096	0,115	
17th	0,007	0,088	0,023	0,310	0,132	
18th	0,010	0,125	0,008	0,109	0,102	
19th	0,006	0,075	0,044	0,601	0,118	
20th	0,007	0,088	0,007	0,097	0,092	
21th	0,005	0,063	0,008	0,116	0,107	0,160
22th	0,007	0,088	0,006	0,088	0,084	
23th	0,004	0,050	0,011	0,146	0,098	0,147
24th	0,006	0,075	0,007	0,091	0,077	
25th	0,004	0,050	0,009	0,128	0,090	0,135
26th	0,004	0,050	0,007	0,100	0,071	
27th	0,004	0,050	0,010	0,141	0,083	0,124
28th	0,004	0,050	0,008	0,108	0,066	
29th	0,005	0,063	0,010	0,138	0,078	0,117
30th	0,005	0,063	0,008	0,106	0,061	
31th	0,005	0,063	0,008	0,112	0,073	0,109
32th	0,003	0,038	0,010	0,130	0,058	
33th	0,010	0,125	0,010	0,139	0,068	0,102
34th	0,003	0,038	0,008	0,103	0,054	
35th	0,018	0,226	0,008	0,116	0,064	0,096
36th	0,004	0,050	0,009	0,121	0,051	
37th	0,015	0,188	0,010	0,139	0,061	0,091
38th	0,003	0,038	0,008	0,114	0,048	
39th	0,016	0,201	0,011	0,144	0,058	0,087
	· ·	·			•	





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 1			
SSEC	G rating per phase	-6KTL-M0				
	At 45-55% of	rated output	100% of ra	ited output		
	1,0	kW	2,0	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,008	0,189	0,012	0,136	1,080	
3rd	0,012	0,278	0,018	0,211	2,300	
4th	0,006	0,140	0,007	0,081	0,430	
5th	0,009	0,207	0,037	0,424	1,140	
6th	0,005	0,117	0,008	0,090	0,300	
7th	0,007	0,157	0,030	0,342	0,770	
8th	0,004	0,102	0,006	0,068	0,230	
9th	0,009	0,196	0,011	0,128	0,400	
10th	0,005	0,117	0,006	0,073	0,184	
11th	0,007	0,152	0,005	0,062	0,330	
12th	0,005	0,113	0,007	0,085	0,153	
13th	0,006	0,141	0,024	0,278	0,210	
14th	0,005	0,115	0,007	0,082	0,131	
15th	0,007	0,153	0,006	0,072	0,150	
16th	0,004	0,098	0,006	0,069	0,115	
17th	0,007	0,160	0,052	0,592	0,132	
18th	0,005	0,122	0,009	0,098	0,102	
19th	0,006	0,139	0,055	0,632	0,118	
20th	0,005	0,111	0,009	0,106	0,092	
21th	0,006	0,131	0,006	0,071	0,107	0,160
22th	0,005	0,113	0,006	0,070	0,084	
23th	0,007	0,170	0,008	0,088	0,098	0,147
24th	0,006	0,144	0,010	0,110	0,077	
25th	0,007	0,167	0,020	0,226	0,090	0,135
26th	0,006	0,136	0,009	0,098	0,071	
27th	0,006	0,135	0,006	0,072	0,083	0,124
28th	0,006	0,131	0,007	0,078	0,066	
29th	0,006	0,141	0,008	0,097	0,078	0,117
30th	0,006	0,132	0,010	0,118	0,061	
31th	0,005	0,126	0,008	0,097	0,073	0,109
32th	0,007	0,152	0,010	0,109	0,058	
33th	0,007	0,150	0,010	0,109	0,068	0,102
34th	0,004	0,092	0,008	0,088	0,054	
35th	0,005	0,111	0,007	0,085	0,064	0,096
36th	0,005	0,106	0,009	0,098	0,051	
37th	0,005	0,104	0,017	0,189	0,061	0,091
38th	0,004	0,095	0,008	0,095	0,048	
39th	0,004	0,097	0,007	0,085	0,058	0,087
39th 40th	0,004 0,004	0,097 0,086	0,007 0,007	0,085 0,075	0,058 0,046	0,





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

wer Quality. H	armonics.					
			Phase 2			
SSEC	G rating per phase	(rpp)	SUN2000	-6KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output		
	1,0	kW	2,0	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,009	0,204	0,010	0,110	1,080	
3rd	0,025	0,576	0,024	0,273	2,300	
4th	0,007	0,156	0,008	0,090	0,430	
5th	0,009	0,210	0,035	0,400	1,140	
6th	0,005	0,125	0,007	0,081	0,300	
7th	0,008	0,177	0,033	0,378	0,770	
8th	0,005	0,123	0,008	0,090	0,230	
9th	0,007	0,165	0,006	0,066	0,400	
10th	0,006	0,135	0,006	0,070	0,184	
11th	0,007	0,153	0,009	0,100	0,330	
12th	0,005	0,110	0,007	0,082	0,153	
13th	0,006	0,145	0,021	0,240	0,210	
14th	0,005	0,119	0,007	0,080	0,131	
15th	0,007	0,161	0,009	0,098	0,150	
16th	0,005	0,121	0,006	0,073	0,115	
17th	0,007	0,165	0,049	0,562	0,132	
18th	0,006	0,129	0,009	0,105	0,102	
19th	0,006	0,144	0,055	0,629	0,118	
20th	0,005	0,115	0,008	0,095	0,092	
21th	0,008	0,171	0,007	0,082	0,107	0,160
22th	0,005	0,113	0,008	0,094	0,084	,
23th	0,007	0,161	0,010	0,117	0,098	0,147
24th	0,007	0,159	0,010	0,114	0,077	2,
25th	0,008	0,174	0,015	0,170	0,090	0,135
26th	0,006	0,145	0,010	0,109	0,071	3,755
27th	0,009	0,195	0,011	0,129	0,083	0,124
28th	0,005	0,124	0.009	0,101	0,066	3,121
29th	0,006	0,142	0.014	0,163	0,078	0,117
30th	0,006	0,139	0,011	0,124	0,061	3,117
31th	0,006	0,129	0,012	0,138	0,073	0,109
32th	0,006	0.144	0,011	0,128	0,058	3,133
33th	0,007	0,148	0,009	0,098	0,068	0,102
34th	0,005	0,105	0,010	0,112	0,054	0,102
35th	0,005	0,111	0,009	0,104	0,064	0.096
36th	0,005	0,171	0,009	0,123	0,051	0,030
37th	0,005	0,120	0,010	0,110	0,061	0.091
38th	0,003	0,104	0,010	0,104	0,048	0,031
39th	0,004	0,168	0,009	0,170	0,048	0.087
40th	0,007	0,188	0,015	0,170	0,038	0,007






Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 3			
SSE	G rating per phase	(rpp)	SUN2000	-6KTL-M0		
		rated output	100% of ra	ited output		
	1,0	•		kW		,
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lin for odd harmonics and abov
2nd	0,006	0,144	0,009	0,105	1,080	
3rd	0,014	0,319	0,013	0,154	2,300	
4th	0,007	0,160	0,007	0,079	0,430	
5th	0,006	0,128	0,048	0,553	1,140	
6th	0,005	0,116	0,007	0,080	0,300	
7th	0,006	0,141	0,034	0,390	0,770	
8th	0,006	0,128	0,007	0,079	0,230	
9th	0,008	0,173	0,005	0,060	0,400	
10th	0,006	0,130	0,007	0,081	0,184	
11th	0,005	0,120	0,007	0,086	0,330	
12th	0,005	0,114	0,006	0,071	0,153	
13th	0,006	0,141	0,027	0,313	0,210	
14th	0,005	0,114	0,007	0,084	0,131	
15th	0,009	0,217	0,008	0,091	0,150	
16th	0,005	0,122	0,007	0,081	0,115	
17th	0,007	0,156	0,049	0,567	0,132	
18th	0,006	0,135	0,007	0,077	0,102	
19th	0,005	0,124	0,055	0,630	0,118	
20th	0,006	0,135	0,009	0,099	0,092	
21th	0,007	0,160	0,006	0,064	0,107	0,160
22th	0,006	0,149	0,008	0,089	0,084	
23th	0,006	0,148	0,008	0,095	0,098	0,147
24th	0,007	0,156	0,008	0,089	0,077	
25th	0,007	0,156	0,016	0,186	0,090	0,135
26th	0,007	0,163	0,008	0,093	0,071	
27th	0,010	0,218	0,007	0,086	0,083	0,124
28th	0,006	0,142	0,008	0,095	0,066	
29th	0,005	0,126	0,017	0,191	0,078	0,117
30th	0,005	0,122	0,010	0,112	0,061	
31th	0,005	0,114	0,012	0,133	0,073	0,109
32th	0,005	0,118	0,008	0,093	0,058	
33th	0,013	0,289	0,008	0,092	0,068	0,102
34th	0,005	0,108	0,009	0,107	0,054	
35th	0,005	0,123	0,009	0,100	0,064	0,096
36th	0,006	0,137	0,008	0,097	0,051	, ,
37th	0,005	0,113	0,015	0,174	0,061	0,091
38th	0,005	0,107	0,007	0,086	0,048	
39th	0,007	0,159	0,008	0,090	0,058	0,087
40th	0,005	0,107	0,007	0,086	0,046	





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 1			
SSE	G rating per phase	(rpp)	SUN2000	-8KTL-M0		
		rated output	100% of ra	ited output		
	1,3	•		kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lin for odd harmonics and abov
2nd	0,038	0,645	0,017	0,145	1,080	
3rd	0,017	0,290	0,023	0,198	2,300	
4th	0,016	0,268	0,009	0,077	0,430	
5th	0,026	0,447	0,058	0,502	1,140	
6th	0,005	0,084	0,006	0,048	0,300	
7th	0,033	0,564	0,031	0,264	0,770	
8th	0,012	0,203	0,006	0,052	0,230	
9th	0,007	0,124	0,016	0,134	0,400	
10th	0,017	0,292	0,007	0,063	0,184	
11th	0,014	0,247	0,007	0,060	0,330	
12th	0,007	0,124	0,006	0,050	0,153	
13th	0,023	0,388	0,030	0,261	0,210	
14th	0,004	0,076	0,006	0,056	0,131	
15th	0,007	0,122	0,005	0,046	0,150	
16th	0,007	0,120	0,007	0,060	0,115	
17th	0,069	1,169	0,026	0,219	0,132	
18th	0,007	0,118	0,009	0,073	0,102	
19th	0,045	0,761	0,034	0,293	0,118	
20th	0,006	0,103	0,010	0,083	0,092	
21th	0,006	0,107	0,008	0,069	0,107	0,160
22th	0,007	0,111	0,008	0,067	0,084	·
23th	0,009	0,158	0,009	0,077	0,098	0,147
24th	0,007	0,120	0,011	0,096	0,077	
25th	0,015	0,247	0,015	0,131	0,090	0,135
26th	0,011	0,188	0,010	0,085	0,071	·
27th	0,007	0,127	0,009	0,075	0,083	0,124
28th	0,011	0,183	0,010	0,083	0,066	
29th	0,012	0,210	0,009	0,073	0,078	0,117
30th	0,009	0,146	0,014	0,124	0,061	
31th	0,010	0,163	0,016	0,138	0,073	0,109
32th	0,020	0,333	0,014	0,120	0,058	
33th	0,008	0,134	0,011	0,091	0,068	0,102
34th	0,014	0,234	0,011	0,097	0,054	,
35th	0,009	0,156	0,012	0,099	0,064	0,096
36th	0,007	0,121	0,014	0,120	0,051	, -
37th	0,012	0,196	0,010	0,084	0,061	0,091
38th	0,012	0,208	0,014	0,118	0,048	,
39th	0,011	0,187	0,014	0,121	0,058	0,087
40th	0,012	0,198	0,010	0,090	0,046	





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 2			
SSE	G rating per phase	(rpp)	SUN2000	-8KTL-M0		
		At 45-55% of rated output 100% of rated output		ited output		
		1,3 kW 2,6 kW				
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lir for odd harmonics and abov
2nd	0,023	0,391	0,015	0,129	1,080	
3rd	0,010	0,162	0,027	0,232	2,300	
4th	0,016	0,268	0,010	0,082	0,430	
5th	0,027	0,458	0,053	0,459	1,140	
6th	0,005	0,090	0,007	0,059	0,300	
7th	0,029	0,496	0,033	0,283	0,770	
8th	0,016	0,266	0,006	0,055	0,230	
9th	0,016	0,274	0,007	0,060	0,400	
10th	0,018	0,302	0,007	0,058	0,184	
11th	0,014	0,232	0,006	0,049	0,330	
12th	0,008	0,131	0,006	0,051	0,153	
13th	0,022	0,372	0,029	0,252	0,210	
14th	0,007	0,121	0,008	0,066	0,131	
15th	0,006	0,095	0,009	0,075	0,150	
16th	0,007	0,111	0,007	0,064	0,115	
17th	0,069	1,176	0,020	0,175	0,132	
18th	0,006	0,106	0,007	0,061	0,102	
19th	0,045	0,764	0,036	0,308	0,118	
20th	0,007	0,124	0,009	0,075	0,092	
21th	0,008	0,130	0,011	0,094	0,107	0,160
22th	0,007	0,114	0,008	0,065	0,084	,
23th	0,010	0,166	0,009	0,075	0,098	0,147
24th	0,008	0,138	0,009	0,074	0,077	,
25th	0,014	0,245	0,017	0,148	0,090	0,135
26th	0,012	0,198	0,009	0,076	0,071	.,
27th	0,008	0,136	0,008	0,072	0,083	0,124
28th	0,013	0,220	0,011	0,093	0,066	-,
29th	0,009	0,152	0,012	0,106	0,078	0,117
30th	0,007	0,123	0,013	0,108	0,061	3,111
31th	0,008	0,134	0,016	0,138	0,073	0,109
32th	0,010	0,172	0,015	0,128	0,058	3,100
33th	0,009	0,147	0,012	0,104	0,068	0,102
34th	0,010	0,174	0,011	0,098	0,054	0,102
35th	0,007	0,122	0,017	0,146	0,064	0.096
36th	0,008	0,143	0,017	0,125	0,051	0,000
37th	0,000	0,206	0,013	0,100	0,061	0,091
38th	0,012	0,236	0,012	0,132	0,048	0,031
39th	0,008	0,230	0,013	0,132	0,048	0,087
40th	0,013	0,216	0,011	0,092	0,046	0,007





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

wer Quality. H	armonics.					
			Phase 3			
SSEC	G rating per phase	(rpp)	SUN2000	-8KTL-M0		
	At 45-55% of	rated output	100% of ra	ited output		
	1,3	kW	2,6	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher limi for odd harmonics 2 and above
2nd	0,031	0,525	0,007	0,065	1,080	
3rd	0,012	0,213	0,018	0,159	2,300	
4th	0,014	0,234	0,008	0,066	0,430	
5th	0,035	0,598	0,074	0,636	1,140	
6th	0,006	0,095	0,007	0,063	0,300	
7th	0,033	0,554	0,035	0,300	0,770	
8th	0,013	0,220	0,006	0,048	0,230	
9th	0,007	0,122	0,007	0,058	0,400	
10th	0,018	0,301	0,006	0,055	0,184	
11th	0,011	0,181	0,007	0,063	0,330	
12th	0,005	0,093	0,006	0,053	0,153	
13th	0,025	0,433	0,032	0,276	0,210	
14th	0,006	0,106	0,006	0,054	0,131	
15th	0,008	0,141	0,008	0,071	0,150	
16th	0,006	0,108	0,008	0,069	0,115	
17th	0,070	1,198	0,025	0,218	0,132	
18th	0,006	0,105	0,007	0,061	0,102	
19th	0,046	0,786	0,034	0,296	0,118	
20th	0,007	0,123	0,008	0,070	0,092	
21th	0,006	0,094	0,007	0,060	0,107	0,160
22th	0,007	0,119	0,008	0,072	0,084	,
23th	0,011	0,179	0,008	0,067	0,098	0,147
24th	0,007	0,118	0,007	0,064	0,077	-,
25th	0,014	0,231	0,017	0,145	0,090	0,135
26th	0,009	0,159	0,010	0,084	0,071	2,122
27th	0,008	0,128	0,010	0,083	0,083	0,124
28th	0,010	0,171	0,010	0,086	0,066	-,:-:
29th	0,010	0,176	0,014	0,123	0,078	0,117
30th	0,007	0,122	0,012	0,103	0,061	0,117
31th	0,007	0,119	0,014	0,117	0,073	0,109
32th	0,014	0,239	0,011	0,098	0,058	5,100
33th	0,006	0,099	0,011	0,099	0,068	0,102
34th	0,013	0,216	0,011	0,116	0,054	5,102
35th	0,008	0,141	0,015	0,134	0,064	0.096
36th	0,008	0,141	0,013	0,134	0,051	0,090
37th	0,007	0,174	0,010	0,083	0,061	0,091
38th	0,010	0,174	0,010	0,083	0,048	0,031
39th	0,009	0,154	0,013	0,131	0,048	0,087
40th	0,009	0,134	0,013	0,115	0,038	0,007





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 1			
SSEC	SSEG rating per phase (rpp) SUN2000-10KTL-M					
	At 45-55% of	rated output	100% of rated output			
	1,6	kW	3,3	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher limi for odd harmonics 2 and above
2nd	0,015	0,203	0,030	0,207	1,080	
3rd	0,017	0,233	0,043	0,299	2,300	
4th	0,007	0,097	0,010	0,070	0,430	
5th	0,041	0,552	0,017	0,117	1,140	
6th	0,007	0,102	0,008	0,054	0,300	
7th	0,031	0,420	0,011	0,074	0,770	
8th	0,005	0,069	0,007	0,048	0,230	
9th	0,008	0,111	0,010	0,069	0,400	
10th	0,006	0,076	0,007	0,050	0,184	
11th	0,032	0,432	0,010	0,071	0,330	
12th	0,006	0,084	0,007	0,047	0,153	
13th	0,013	0,173	0,009	0,064	0,210	
14th	0,007	0,094	0,006	0,044	0,131	
15th	0,009	0,122	0,006	0,044	0,150	
16th	0,006	0,086	0,008	0,057	0,115	
17th	0,032	0,443	0,009	0,062	0,132	
18th	0,006	0,079	0,007	0,048	0,102	
19th	0,048	0,655	0,008	0,055	0,118	
20th	0,008	0,112	0,006	0,043	0,092	
21th	0,011	0,144	0,006	0,043	0,107	0,160
22th	0,006	0,085	0,007	0,047	0,084	
23th	0,012	0,165	0,009	0,063	0,098	0,147
24th	0,007	0,092	0,008	0,053	0,077	
25th	0,012	0,160	0,008	0,059	0,090	0,135
26th	0,009	0,118	0,006	0,043	0,071	·
27th	0,009	0,119	0,009	0,061	0,083	0,124
28th	0,008	0,103	0,008	0,056	0,066	·
29th	0,010	0,130	0,008	0,055	0,078	0,117
30th	0,010	0,142	0,009	0,064	0,061	
31th	0,009	0,120	0,009	0,060	0,073	0,109
32th	0,010	0,132	0,009	0,062	0,058	
33th	0,009	0,125	0,013	0,089	0,068	0,102
34th	0,008	0,108	0,013	0,090	0,054	
35th	0,009	0,121	0,048	0,330	0,064	0,096
36th	0,009	0,128	0,017	0,121	0,051	
37th	0,007	0,102	0,026	0,178	0,061	0,091
38th	0,010	0,141	0,011	0,075	0,048	
39th	0,009	0,127	0,025	0,171	0,058	0,087





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

			Phase 2			
SSE	G rating per phase	(rpp)	SUN2000-	10KTL-M0		
		rated output				
	1,6	•		kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lin for odd harmonics and abov
2nd	0,010	0,140	0,016	0,113	1,080	
3rd	0,025	0,345	0,016	0,110	2,300	
4th	0,007	0,101	0,012	0,084	0,430	
5th	0,036	0,492	0,018	0,124	1,140	
6th	0,007	0,093	0,009	0,060	0,300	
7th	0,030	0,413	0,009	0,063	0,770	
8th	0,006	0,078	0,009	0,062	0,230	
9th	0,007	0,091	0,014	0,096	0,400	
10th	0,006	0,081	0,008	0,057	0,184	
11th	0,030	0,405	0,010	0,069	0,330	
12th	0,006	0,087	0,007	0,049	0,153	
13th	0,014	0,194	0,012	0,085	0,210	
14th	0,007	0,089	0,008	0,058	0,131	
15th	0,009	0,118	0,007	0,047	0,150	
16th	0,007	0,097	0,008	0,058	0,115	
17th	0,029	0,392	0,009	0,060	0,132	
18th	0,009	0,123	0,007	0,048	0,102	
19th	0,045	0,607	0,009	0,063	0,118	
20th	0,010	0,134	0,007	0,045	0,092	
21th	0,008	0,103	0,007	0,045	0,107	0,160
22th	0,007	0,098	0,007	0,049	0,084	,
23th	0,011	0,143	0,009	0,059	0,098	0,147
24th	0,007	0,092	0,008	0,052	0,077	,
25th	0,012	0,164	0,009	0,064	0,090	0,135
26th	0,007	0,102	0,007	0,050	0,071	,
27th	0,008	0,109	0,010	0,069	0,083	0,124
28th	0,008	0,102	0,010	0,071	0,066	,
29th	0,007	0,100	0,008	0,057	0,078	0,117
30th	0,011	0,148	0,011	0,074	0,061	·
31th	0,007	0,096	0,010	0,070	0,073	0,109
32th	0,010	0,130	0,018	0,126	0,058	
33th	0,009	0,117	0,014	0,096	0,068	0,102
34th	0,009	0,118	0,018	0,121	0,054	,
35th	0,008	0,112	0,048	0,331	0,064	0,096
36th	0,009	0,118	0,020	0,141	0,051	
37th	0,010	0,134	0,042	0,290	0,061	0,091
38th	0,010	0,133	0,025	0,174	0,048	-,
39th	0,008	0,112	0,015	0,102	0,058	0,087
40th	0,010	0,135	0,025	0,172	0,046	,





Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

wer Quality. H	armonics.					
			Phase 3			
SSEC	G rating per phase	(rpp)	SUN2000-	10KTL-M0		
	At 45-55% of	rated output	100% of rated output			
	1,6	kW	3,3	kW		
Harmonic	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Measured Value (MV) in [A]	Measured Value (MV) in [%]	Limit in BS EN61000-3-2 in Amps	Higher lim for odd harmonics and above
2nd	0,015	0,200	0,025	0,173	1,080	
3rd	0,009	0,126	0,036	0,246	2,300	
4th	0,007	0,095	0,015	0,102	0,430	
5th	0,048	0,654	0,016	0,110	1,140	
6th	0,005	0,070	0,008	0,053	0,300	
7th	0,035	0,482	0,012	0,080	0,770	
8th	0,006	0,079	0,009	0,063	0,230	
9th	0,006	0,079	0,008	0,055	0,400	
10th	0,005	0,069	0,008	0,055	0,184	
11th	0,029	0,398	0,011	0,076	0,330	
12th	0,005	0,075	0,007	0,050	0,153	
13th	0,010	0,137	0,012	0,081	0,210	
14th	0,006	0,083	0,008	0,057	0,131	
15th	0,007	0,103	0,009	0,059	0,150	
16th	0,007	0,096	0,007	0,051	0,115	
17th	0,023	0,310	0,008	0,053	0,132	
18th	0,008	0,109	0,008	0,054	0,102	
19th	0,044	0,601	0,009	0,061	0,118	
20th	0,007	0,097	0,007	0,046	0,092	
21th	0,008	0,116	0,009	0,061	0,107	0,160
22th	0,006	0,088	0,007	0,050	0,084	-,
23th	0,011	0,146	0,009	0,065	0,098	0,147
24th	0,007	0,091	0,007	0,050	0,077	2,
25th	0,009	0,128	0,009	0,065	0,090	0,135
26th	0,007	0,100	0,007	0,048	0,071	3,100
27th	0,010	0,141	0,008	0,059	0,083	0,124
28th	0.008	0,108	0,010	0,070	0,066	3,121
29th	0,010	0.138	0.009	0,062	0,078	0,117
30th	0,008	0,106	0,011	0,077	0,061	0,117
31th	0,008	0,112	0,010	0,071	0,073	0,109
32th	0,010	0,130	0.017	0,119	0,058	3,100
33th	0,010	0,139	0,017	0,088	0,068	0,102
34th	0,008	0,103	0,015	0,105	0,054	0,102
35th	0,008	0,116	0,036	0,248	0,064	0.096
36th	0,008	0,110	0,036	0,248	0,051	0,030
37th	0,009	0,121	0,016	0,110	0,061	0,091
38th	0,008	0,139	0,037	0,233	0,048	0,031
39th	0,008	0,114	0,026	0,110	0,048	0.087
40th	0,009	0,144	0,018	0,135	0,038	0,007





Extract from test report according to the Engineering Recommendation G98/1-1

Power Quality. Pov	wer factor.			
SUN2000-3KTL				
Output power	216,2V	230V	253V	Measured at three voltage levels and at full
20%	0,9955	0,9962	0,9951	output. Voltage to be maintained within ±1,5% of the stated level during the test.
50%	0,9991	0,9992	0,9991	
75%	0,9996	0,9996	0,9996	
100%	0,9998	0,9998	0,9998	
Limit	>0,95	>0,95	>0,95	
SUN2000-10KTL			•	
Output power	216,2V	230V	253V	Measured at three voltage levels and at full
20%	0,9996	0,9996	0,9995	output. Voltage to be maintained within ±1,5% of the stated level during the test.
50%	0,9999	0,9993	0,9999	
75%	0,9999	0,9997	0,9999	
100%	0,9999	0,9998	0,9999	
Limit	>0,95	>0,95	>0,95	

CUNOCOC CICTU MO		Starting			Stopping			Running		
SUN2000-3KTL-M0	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours		
Measured values at test impedance Phase 1	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,07	0,07		
Measured values at test impedance Phase 2	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,07	0,07		
Measured values at test impedance Phase 3	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,07	0,07		
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65		
SUN2000-4KTL-M0		Starting			Stopping			Running		
5UN2UUU-4K I L-IVIU	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours		
Measured values at test impedance Phase 1	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,08	0,07		
Measured values at test impedance Phase 2	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,07	0,07		
Measured values at test impedance Phase 3	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,07	0,07		
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65		





Extract from test report according to the Engineering Recommendation G98/1-1

OUNIOSOS SIZTI MO		Starting			Stopping		Ru	nning	
SUN2000-5KTL-M0	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours	
Measured values at test impedance Phase 1	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 2	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 3	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65	
SUN2000-6KTL-M0	Starting			Stopping		Ru	nning		
OUNTERNO	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours	
Measured values at test impedance Phase 1	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 2	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 3	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65	
SUN2000-8KTL-M0	Starting			Stopping			Running		
	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours	
Measured values at test impedance Phase 1	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 2	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Measured values at test impedance Phase 3	0,00%	0,00%	0,00%	0,00%	0,00%	0,00%	0,7	0,7	
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65	
SUN2000-10KTL-M0		Starting			Stopping		Ru	nning	
CONZOCO TOTALE INIC	dmax	dc	d(t)	dmax	dc	d(t)	Pst	Plt 2 hours	
Measured values at test impedance Phase 1	0,29%	0,23%	0,00%	0,29%	0,23%	0,00%	0,8	0,8	
Measured values at test impedance Phase 2	0,29%	0,31%	0,00%	0,29%	0,31%	0,00%	0,8	0,8	
Measured values at test impedance Phase 3	0,34%	0,32%	0,00%	0,34%	0,32%	0,00%	0,8	0,8	
Limits set under BS EN 61000-3-11	4%	3,3%	3,3% 500ms	4%	3,3%	3,3% 500ms	1,0	0,65	





Extract from test report according to the Engineering Recommendation G98/1-1

Power Quality. DC injection.								
SUN2000-10KTL-M0	SUN2000-10KTL-M0							
Test level power [%]	20	50	75	100				
Recorded value [mA] Phase 1	4,5	4,2	4,2	4,0				
Recorded value [%]Phase 1	0,08	0,08	0,08	0,08				
Recorded value [mA] Phase 2	4,2	4,1	4,3	4,1				
Recorded value [%]Phase 2	0,08	0,08	0,08	0,08				
Recorded value [mA] Phase 3	1,2	1,2	0,7	0,8				
Recorded value [%]Phase 3	0,02	0,02	0,01	0,02				
Limit [%]	0,25	0,25	0,25	0,25				
SUN2000-3KTL-M0								
Test level power [%]	20	50	75	100				
Recorded value [mA] Phase 1	3,4	3,7	3,8	5,8				
Recorded value [%]Phase 1	0,02	0,02	0,02	0,03				
Recorded value [mA] Phase 2	3,9	3,1	3,5	5,3				
Recorded value [%]Phase 2	0,02	0,02	0,02	0,03				
Recorded value [mA] Phase 3	1,4	1,7	3,1	4,7				
Recorded value [%]Phase 3	0,01	0,01	0,02	0,03				
Limit [%]	0,25	0,25	0,25	0,25				

Fault level Contribution.	Fault level Contribution.								
SUN2000-10KTL-M0 Phase 1									
For a directly coup	led SSEG		For a Inverter SS	SEG					
Parameter	Symbol	Value	Time after fault	Volts [V]	Amps [A]				
Peak Short Circuit current	Ip	N/A	20ms	54	12,9				
Initial Value of aperiodic current	А	N/A	100ms	39	7,7				
Initial symmetrical short-circuit current*	lk	N/A	250ms	N/A	N/A				
Decaying (aperiodic) component of short circuit current*	i _{DC}	N/A	500ms	N/A	N/A				
Reactance/Resistance Ratio of source*	X/R	N/A	Time to Trip [s]	0,074					



Appendix C Type Test Verification Report

Extract from test report according to the Engineering Recommendation G98/1-1

Nr. PVUK180906N022

SUN2000-10KTL-M0 Phase 2							
For a directly coup	led SSEG			For a Inverter SSEG			
Parameter	Symbol	Value	Time after fault	Volts [V]	Amps [A]		
Peak Short Circuit current	Ip	N/A	20ms	49	13,1		
Initial Value of aperiodic current	А	N/A	100ms	38	8,2		
Initial symmetrical short-circuit current*	I _k	N/A	250ms	N/A	N/A		
Decaying (aperiodic) component of short circuit current*	i _{DC}	N/A	500ms	N/A	N/A		
Reactance/Resistance Ratio of source*	X/R	N/A	Time to Trip [s]	0,074			
SUN2000-10KTL-M0 Phase 3			<u> </u>				
For a directly coup	led SSEG			For a Inverter SS	EG		
Parameter	Symbol	Value	Time after fault	Volts [V]	Amps [A]		
Peak Short Circuit current	Ip	N/A	20ms	37	13,3		
Initial Value of aperiodic current	Α	N/A	100ms	35	7,7		
Initial symmetrical short-circuit current*	I _k	N/A	250ms	N/A	N/A		
Decaying (aperiodic) component of short circuit current*	i _{DC}	N/A	500ms	N/A	N/A		
Reactance/Resistance Ratio of	Y/R	N/A	Time to	0.074			

For rotating machines and linear piston machines the test should produce a 0s – 2s plot of the short circuit current as seen at the Generating Unit terminals.

Trip [s]

0.074

N/A

X/R

^{*} Values for these parameters should be provided where the short circuit duration is sufficiently long to enable interpolation of the plot.

Self Monitoring – Solid state switching.	N/A
It has been verified that in the event of the solid state switching device failing to disconnect the Generating Unit, the voltage on the output side of the switching device is reduced to a value below 50 volts within 0,5 seconds.	

Note. Unit do not provide solid state switching relays. In case the semiconductor bridge is switched off, then the voltage on the output drops to 0. In this case the relays on the output will also open.

Additional comments

source*

The models SUN2000-3KTL-M1, SUN2000-4KTL-M1, SUN2000-5KTL-M1, SUN2000-6KTL-M1, SUN2000-8KTL-M1 and SUN2000-10KTL-M1 are almost identical in hardware with SUN2000-3KTL-M0, SUN2000-4KTL-M0, SUN2000-5KTL-M0, SUN2000-6KTL-M0, SUN2000-8KTL-M0, and SUN2000-10KTL-M0 except the PLC communication circuit. (J6 port and a Hi3911V200 chip)